

TENDER  
FOR

SUPPLY, SUPERVISION & COMMISSIONING OF  
TRANSFORMER & H.T. BREAKER,  
SECRETARIAT, CAPITOL COMPLEX

NAYA RAIPUR, CHHATTISGARH

VOLUME III

PRICE BID

(To Be Submitted With Envelope # 2)

NOVEMBER 2009

Tender No.\_\_\_\_/CEO/NRDA/2009-10

SUMMARY OF TOTAL PRICES		
SECTION NO	DESCRIPTION OF WORK	AMOUNT (Rs.)
1	TRANSFORMER SUPPLY	
2	33KV H.T. PANEL SUPPLY	
GRAND TOTAL		
AMOUNT IN WORDS :		
SIGNATURE AND STAMP OF THE TENDERER		

**BILL OF QUANTITIES - TRANSFORMER AND H.T. PANEL SUPPLY**

All items of BOQ shall be read in conjunction with the technical specifications. Rates shall be including all necessary taxes.

Sr.No.	Description	Qty	Unit	Rate	Amount
<b>SECTION - 1.0 TRANSFORMER SUPPLY</b>					
	This includes the scope of preparation of drawings, supply of equipments as listed below. The equipment shall be supplied from factory, unloaded from transport shifted to store. Commissioning of the transformers shall be done by electrical contractor (third party) at site. Though supervision of comissioning for 2 days per transformer shall be included in the scope of supplier. All necessary cost for supervisor - lodging / boarding / per diem charges etc. shall be included in the rates. Charges for factory inspection of goods prior to dispatch for three persons (lodging / boarding from port of residence / hotel stay / local conveyance) shall be included in the offer.				
1.1	1600KVA 33/0.415KV, DYN11 indoor cast resin dry type transformer with off load tap changer including all necessary accessories as per specification of the tender.	1	no		
<b>Rate in words</b>					
1.2	-do- as above but 1250 KVA	1	no		
<b>Rate in words</b>					
1.3	-do- as above but 2000 KVA	2	no		
<b>Rate in words</b>					
<b>TOTAL OF SECTION 1.0</b>				<b>Rs.</b>	
<b>Amount in words</b>					

Sr.No.	Description	Qty	Unit	Rate	Amount
<b>SECTION - 2.0 33KV H.T. PANEL SUPPLY</b>					
	This includes the scope of preparation of drawings, supply of equipments as listed below. The equipment shall be supplied from factory, unloaded from transport shifted to store. Commissioning of the H.T. panel shall be done by electrical contractor (third party) at site. Though supervision of commissioning for 2 days for panel shall be included in the scope of supplier. All necessary cost for supervisor - lodging / boarding / per diem charges etc. shall be included in the rates. Charges for factory inspection of goods prior to dispatch for three persons (lodging / boarding from port of residence / hotel stay / local conveyance) shall be included in the offer.				
2.1	Supply of indoor type VCB panel of 33KV 7 breaker panel with 2 nos incoming breaker of 630A (ct ratio - 120/1/1) and outgoing breaker 4 nos of 630A (CT ratio 30/1/1 for 1 feeder and 40/1/1/ for three feeders) and 1 bus coupler breaker of 630A with bus PT complete as per specifications and SLD. All the breakers shall be 26.2 KA and shall be with all metering / relays / power pack etc as indicated in the specification sheet.	1	no		
<b>Rate in words</b>					
<b>TOTAL OF SECTION 2.0</b>					
					<b>Rs.</b>
<b>Amount in words</b>					
<b>GRAND TOTAL OF 1 &amp; 2</b>					
					<b>Rs.</b>
<b>Amount in words</b>					
<p>All above rates shall be inclusive of:</p> <ul style="list-style-type: none"> <li>i) Basic price for shop drawings &amp; equipment engineering</li> <li>ii) Price for special decibel test for noise</li> <li>iii) Packing and forwarding</li> <li>iv) Excise duty, Sales Tax, Octroi, Transit Insurance etc</li> <li>v) Transport upto site, loading &amp; unloading</li> <li>vi) Supervision charges for providing engineer during installation and commissioning</li> <li>vii) Spare parts as stated under relevant clause of Volume II</li> </ul>					